BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2023-24/SE0077/CALL-2

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/KPPP/11/2023-24, Date: 06-11-2023

Name of Work: Supplying and Laying of various bituminous mixes for repair of potholes and Road cut Portions from established Hot Mix Plant of minimum 50/80 TPH capacity (In Fully working condition) including manufacturing, supplying and laying including the cost of all materials, machineries, labours, consumables etc complete for a period of 2 years in Byatarayanapura Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of M/s. MSV Construction Company	
				In Figures	In Words
1	1.00	Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 503, back filling the pot holes with hot bituminous material as per clause 504, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 for Grading ll Material PWD CSR 21-22 VOl 3 it. No 10.5 Page No 76 (as per Issue Rates Dated 01-01-2023)	SQ.MTR	450	Rupees Four Hundred Fifty Only
2	1.00	Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 503, back filling the pot holes with 75 mm of Wet Mix Macadam and Bituminous material as per clause 504, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 for Grading ll Material including all lead, lift and cost of materials and labour etc.,	SQ.MTR	410	Rupees Four Hundred Ten Only
3	1.00	Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 503, back filling the pot holes with 100 mm of Wet Mix Macadam and Bituminous material as per clause 504, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 for Grading ll Material including all lead, lift and cost of materials and labour etc.	SQ.MTR	540	Rupees Five Hundred Forty Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
Bruhat Bengaluru Mahanagara Palike